



September 29, 2025

City of Joliet
150 W. Jefferson St.
Joliet, IL

RE:	Joliet Slammers RTU Replacement
ATTN:	Blaine Kline
Tax Exempt:	No

As requested, we are pleased to provide a proposal for replacing the (5) rooftop units listed below.

RTU 1-2 – SN R44101526D (12.5-ton)
RTU 1-3 – SN Z50100951D (17.5-ton)
RTU 3-1 – SN Z50100959D (20-ton)
RTU 3-2 – SN Z50101247D (25-ton)
RTU 3-3 – SN Z50100920D (20-ton)

Scope of Work

- Disconnect, remove, and haul away the existing RTUs.
- Furnish and install direct replacements for the existing RTUs. The replacements will include low-leak economizers and hail guards.
- Furnish and install roof curb adapters as required.
- Replace the electrical disconnects on each of the five units.
- Connect the new unit to the existing gas, ductwork, control wiring, and power.
- Provide a crane as required to lift the roof equipment. Street closure permits and traffic control are included.
- Startup and verify the operation of the equipment.

General Items

- All work will be performed during regular working hours, Monday through Friday.
- This proposal carries our standard one-year warranty for equipment replacements.
- If further repairs to existing equipment are needed for proper operation, they will be completed on a Time and Material or Quoted basis once building management approves.

Total Investment: \$271,500



Exclusions:

- Overtime
- Roofing
- Preventive Maintenance
- Temporary Heating & Cooling

Thank you for the opportunity to serve you. If there is anything else we can help with, please call.
Sincerely,



Award@wsmech.com

(630) 401-0776



ROkon@wsmech.com

815-409-5843

Sales/Piping Manager

To accept this quotation, sign here and return:

Signature: _____

Print Name: _____

Date: _____