



April 1, 2026

Joliet Fire Department
101 E. Clinton
Joliet, IL 60432

Phone:
Fax:

Attention: Capt. Burke J. Schuster
Regarding: Stations 1 & 9 Painting
Architect:

Bid #: 26-MB-175

We submit herewith our proposal for the labor, material, equipment, insurance, and adhering to all O.S.H.A. safety standards and regulations for the painting work on the above referenced project. Our bid is based on: sheets jobsite visits, standard painting specification 09900, ATD’s standard insurance coverage (certificate available upon request), and that all inclusions and exclusions listed below are to be incorporated into any contract awarded.

All for the base bid amount of \$75,025

Break outs (included in base bid):

Station 1.....	\$ 35,612
Station 9	\$ 39,413

ALTERNATES (not included in base bid):

Deduct to paint Sherwin Williams ProMar 200 from 0'-7' in lieu of PreCat Epoxy (\$350)/ station

Base Bid Inclusions:

- Proper Sequence and coordination of trades.
- Standard painters prep only (minor spackling and sanding).

Station 1 – Bay area and laundry room

- Two lift rentals included
- Patch CMU holes with caulk and paint over
- Paint Sherwin Williams PreCat Epoxy on walls 0’- 7’ in bay area- 2 color scheme
- Paint Sherwin Williams Pro Mar 200 on walls from 7’ to ceiling in bay area- 2 color scheme
- Paint Sherwin Williams PreCat Epoxy on walls in the laundry room
- Patch and paint Sherwin Williams ProMar200 E/S on ceilings
- Paint hollow metal doors and frames with a split finish- safety red and TBD. Sherwin Williams Industrial Enamel
- Paint borrowed light frame. Sherwin Williams Industrial Enamel

Station 9 – Bay area, laundry room, utility room , & dispatch

- Two lift rentals included
- Patch CMU holes with caulk and paint over
- Patch and paint Sherwin Williams ProMar200 E/S on ceilings
- Paint Sherwin Williams PreCat Epoxy on walls 0’- 7’ in bay area- 1 color scheme
- Paint Sherwin Williams ProMar 200 on walls from 7’ to ceiling in bay area-1 color scheme
- Paint Sherwin Williams PreCat Epoxy on walls in the laundry room and utility room
- Paint Sherwin Williams ProMar 200 on walls in dispatch room
- Paint bay side only of 8 hollow metal door frames. Paint both sides of 3 doors and frames

Base Bid Exclusions:

- Transparent door and millwork finishes
- Any floor coatings
- Overtime
- Damage done by others
- Conduit

We thank you for the opportunity to submit this proposal to you.

Respectfully Submitted By,
ALL-TECH DECORATING CO.



Mike Buralli
Project Manager/Estimator
Direct Line: 779-875-0680

'Committed to Excellence'

See *Excellence* in action! >>> www.alltechdecorating.com

Our mission is to provide unparalleled value in the painting industry, driven by Safety, Exceptional Customer Service, Quality Craftsmanship and **Environmental** Responsibility.